BRUHAT BENGALURU MAHANAGARA PALIKE

BYATARAYANA PURA DIVISION

Name of work:Improvements To Roads And Drains at Shivapura and Surrounding Area in Ward No.05 Jakkur

DRAFT TENDER SCHEDULE

Sl No	Description of Items	Unit	Qty	Rate in Rs	
				Rate in Figures	Rate in Words
1	Earthwork excavation by manual means for roads, drains & similar works in ordinary soil invoiving , excavated surface leveled & sides neatly dressed , the disposed earth to be levelled neatly after breaking of clods complete as per specification MORTH/ Chapter 3. As Per the Direction of Engineer In charge of the work.	Cum	1230.30	220.40	Rupees Two Hundred Twenty And Paise Forty Only
2	Providing and laying Plain cement concrete of mix 1:3:6 with OPC @ 220kgs, with crushed 40mm and down size graded granite metal coarse aggregates @0.89cum and fine aggregates @ 0.46cum, in foundation mechanically mixed, placed in foundation and compacted by vibration including curing for 14 days including cost of all materials, labour, HOM curing, form works, scaffolding and centering complete as per specifications. As Per the Direction of Engineer In charge of the work.	Cum	184.55	5509.33	Rupees Five Thousand Five Hundred Nine And Paise Thirty Three Only
3	Providing and laying plain/reinforced cement concrete for side drains using M20 nominal mix concrete with OPC at 300 kgs. with 20mm and down size granite metal coarse aggregates at 0.69 cum and fine aggregates at 0.43 cum machine mixed, well compacted for walls and bottom including centering, shuttering, cost of materials, HOM of machinery, curing etc., complete excluding cost of steel as per MORTH specification No. 1500, 1700, 2200. including cost of materials, labour, HOM complete as per specificationsdo- Wall & bottom thickness 15cm.As Per the Direction of Engineer In charge of the work.	Cum	396.77	7189.42	Rupees Seven Thousand One Hundred Eighty Nine And Paise Forty Two Only
4	Providing T.M.T steel reinforcement for R.C.C workincluding straightening, cutting, bending, hooking, placing in position,lapping and / or welding wherever required, tying with binding wire andanchoring to the adjoining members wherever necessary complete asper design (laps, hooks and wastage shall not be measured and paid)cost of materials, labour, HOM of machinery complete as perspecifications.Specification No. KBS 4.6.3.As Per the Direction of Engineer In charge of the work.	Tonne	26.25	65046.90	Rupees Sixty Five Thousand Forty Six And Paise Ninety Only

Name of work:Improvements To Roads And Drains at Shivapura and Surrounding Area in Ward No.05 Jakkur					
DRAFT TENDER SCHEDULE					
Sl No	Description of Items	Unit	Qty	Rate in Rs	
				Rate in Figures	Rate in Words
5	Providing and fixing Precast RCC cover slabs of 100 mm thick for drain in cement concrete 1:1.5:3 using graded granite jelly 20mm and down size with steel reinforcement and pointing for joints 1:3 cement mortor including form work, lift charges,curing and concrtee finished surface on both sides etc,and complete as per the directions of Enginner in charges.(Data Rate).As Per the Direction of Engineer In charge of the work.	Sqm	972.90	2337.00	Rupees Two Thousand Three Hundred Thirty Seven Only
6	Providing and fixing Precast RCC slab of 250mm thick for Culverts made of Plain/Reinforced Cement Concrete design mix M25 with OPC@340kgs,with 20mm and down size graded granite metal coarse aggregates @0.70cum and fine aggregates@0.47cum,with superplasticizer@3lts confirming to 189103-1999 Reaffirmed-2008,Open Foundation complete as per Drawing and Technical Specification including cost of all materials, labour,HOM curing,form works,scaffolding and centering complete as per specifications and pointing for ljoints 1:3 cement mortar including form work,lift charges,curing and concrete finished surfaces on both sides etc, (Data Rate). complete and as per the directions of Engineer in-Charge.	Sqm	30.90	5418.00	Rupees Five Thousand Four Hundred Eighteen Only

1. The Work Should be executed as per the specification and standard specified by the PWD & Other Specifications of the Bangalore Mahanagara Palike and as directed.
2. The Work Should be carried out as per the directions and instructions of the concerned Engineer.
3. The Contractor Should Maintain the Quantity of Work as per the Standard Specification.

01/12

Executive Engineer
Byatarayana Pura Division
BBMP - Bangalore

01/12

( ) ರಲ್ಲಿ ವಿವರಿಸಿರುವಂತೆ ಅಂಶಗಳ ಬಗ್ಗೆ
ಕಾರ್ಯಪಾಲಕ ಅಭಿಯಂತರರು( ) ರವರು
ಪರಿಶೀಲಿಸಿಕೊಳ್ಳುವುದು.
ಅಳವಡಿಸಬೇಕಾದ ಒಟ್ಟು ಸಂಖ್ಯೆ : —
ರದ್ದುಗೊಳಿಸಿರುವ ಒಟ್ಟು ಪುಟಗಳ ಸಂಖ್ಯೆ : —
01/12/2020